



## Reference

People Mover

Conductor Rail Hevi-Bar II



### Application

Transfer between two Airport terminals [cable liner system; DCC]

### Country

Canada

### City

Toronto

### Project installation date

2006

### Representative office

Conductix-Wampfler [USA]

### Operator

Doppelmayr [DCC]

### Customer

Siemens, Austria

### Technical requirement[s]

Electrification of the interior equipment of the People Mover

### Product[s]

Conductor Rail, Hevi-Bar II

### Number of [Load]

6

### Travel distance [Load]

2 x 1473 m

### Travel speed [Load]

43,2 km/h

### Number of poles

3 + PE

### Collector assembly

Double collector

### Current

150 A

### Voltage

480 V [AC]

### Additional information

- In operation: 22 hrs./day
- System capacity: 2150 passengers per hour and per direction